

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 56

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

For corners in **COMMISSION**

Benzie (County) Located In: Corner Code #

1. Public Land Survey T 26N R 14W M-7
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/22/1997 1:56:10 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES 1

Register of Deeds Stamp & File Number

John B. Smendzuik, in a field survey on 4/11 and 6/26, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-7: G.L.O. set post and witnesses - 10" Sugar N16°W 5.94', 11" Sugar S76°W 21.78', 8" Sugar N32°E 13.86' and 13" Sugar S55°E 13.20'. Record of Surveys, Page 89, shows work being done in Section 18 in July of 1868. Surveyor's Record II, Page 58, Frank Haswell notes found old post. G.A. Shadko, Michigan Department of Conservation, in June of 1944, found an iron pin and set a D.N.R. concrete monument. Harold Bruning in 1972 and Carl F. Roser in 1988 filed Act 74 records with corner being D.N.R. monument in Liber 1, page 129 and Liber 1, page 248.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-7: Found D.N.R. concrete monument next to a 1/2" iron pipe inside a 3/4" iron pipe 30" long.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman [Signature]
 Date 12/27/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-7: Removed D.N.R. and iron pipe remains, after Road Commission work to rebuild County Road 669, and set a 3" diameter Benzie County Remonumentation Program concrete monument in a monument box.

24" Maple	N68°E	69.53'	5/8" x 24" rebar	N47°E	65.45'
18" Maple	S73°E	89.25'	5/8" x 24" rebar	S47°W	64.05'
Power pole	S30°E	72.51'			

Signed by [Signature] Date 1/21/97
 Surveyor's Michigan License No. 30895