

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Benzie Located In _____ Corner Code # _____
(County)

1. Public Land Survey T 26N R 14W J1
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on April 12, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J1 – GLO – Not set in original survey
- CSR – L. 1, p. 60 – F. Haswell - 1907
Set 1" Galv. iron well point 27 ½ links
E. of ¼ post for T27N, R14W.
- LCRC – L. 1, p. 336 – C. Kiiskila – 1997
Fd. Old 1" well point and added DNR Mon. in exact same spot and set Carsonite Post;
28" B. Cherry N32°E 12.37';
18" Tw. Maple N70° 26.70';
11" R. Pine S37°W 41.28';
S ¼ Sec. 35, T27N, R14W – DNR Mon.-
N88° 37' W 18.15'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J1 – Closing ¼ Corner common to Sec. 2, T26N, R14W – Fd. DNR Monument per Kiiskila at apparent Haswell position. Centerline of E-W 2-track is 18' S. DNR Mon. accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J1 – 4" DNR Alum. Cap on 1" Galv. iron pipe with Blue Carsonite Post alongside
N38°E 12.39' to Fd. nail in W. side 30" B. Cherry (CK)
S70°E 26.73' to Fd. nail in S. side 30' Tw. R. Maple (CK)
S36°W 41.29' to Fd. nail in S. side 14" R. Pine (CK)
West 18.15' to 'J13', T27N, R14W – DNR Mon.



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 5/9/2005

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |