

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Benzie Located In _____ Corner Code # _____
 (County)

- | | | | | |
|--------------------------------------|-------------|--------------|--------------|-----------|
| 1. Public Land Survey | T _____ | R _____ | | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S <u>31</u> | T <u>26N</u> | R <u>14W</u> | <u>16</u> |
| | S _____ | T _____ | R _____ | |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 15, 2009 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:


- 16 – 1909 – CSR L. 2, p. 102 – F. S. Haswell - Drove 1" iron pipe 3' deep halfway and in right line between 3 & 7.
- 1979 – LCRC L. 1, p. 95 – C. F. Roser – Fd. 1" x 36" iron pipe buried in E-W dirt Co. Rd. per Haswell. E 1/8 Cor. on N. line Sec. 5 (25-14) is N89°37'E 207.93'. Center E-W dirt Rd. N 9'±
 - 1) Set Cedar post with loc. tag N. 33'
 - 2) 9" Cherry (Cluster) N45°E 49.4'
 - 3) 12" Maple N10°E 52.4'
 - 4) 5" R. Pine N42°W 57.1'; Old fn. to N. – Due W. 2'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 16 – E 1/16 corner common to S. Line of Sec. 31, T26N, R14W – Fd. 1" iron pipe per Haswell and Roser in E-W rebuilt gravel road. 1" pipe accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 16 – 1" iron pipe
 S80°20'32"E 208.04' to E 1/16, Sec. 6 (25-14) – 2" Alum. Cap
 N45°E 49.69' to set N & T at Fd. N & T in NW side Tri 8", 12" & 12" Cherry (#2)
 N10°E 52.24' to set N & T in W. side 18" S. Maple (#3)
 N55°W 52.93' to set N & T in S. side 14" R. Pine
 North 33' to set Blue Carsonite Post with loc. tag



Signed by: Craig W. McVean Date: 4/21/2010
 Surveyor's Michigan License No.: 39088