

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 15 W.	G-12; H-12
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 26, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- G-12 Computed position for  $W\frac{1}{4}$  of Sec. 34 is in the Betsie River, per single proportion to U.S. to found section corners to N and S. This fits Haswell survey of 1910.
- H-12 Recovered concrete monument in line with approximate center of roads to north and east. Monument has been accepted and used by prior R.L.S.'s in this area, *as the center of Sec. 34.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<i>Wit. Cor. to</i> → G-12 → <i>Wit. Cor. to</i>		H-12
Set $1\frac{1}{4}$ "x72" pipe & ced. post w/loc. tag	Set $1\frac{1}{4}$ "x72" pipe & ced. post w/loc. tag	Found 4" concrete monument
Comp. $\frac{1}{4}$ cor. S00°24'W 58.39	Comp. $\frac{1}{4}$ cor. N88°29'W 56.07	30" Maple N20°E 98.65
10" Cedar N30°W 62.9	10" Hemlock N34°W 35.7	Power Pole S88°W 33.35
7" Cedar N15°W 48.8	7" Maple N08°W 22.9	Set cedar post w/loc. tag
5" Cedar S62°E 33.4	8" Cedar S62°E 22.1	Due S 33.0
45' S to N bank of Betsie Rvr.	26' W to E bank of Betsie Rvr.	

SIGNED BY Carl F. Roser 8-25-75 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ SOUTH PART OF Benzie COUNTY  
 BENZONIA TOWNSHIP