

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>15W</u>	<u>L-5</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Numb,

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on April 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5 -GLO - Set post - Alvin Burt - 1838
Hemlock 8" S30°W 22L
Beech 20" N60°W 16L
-Co. Bk., P. 138-139 -Sec. 13 Survey - F. Haswell - 1894
Drove stake 2' deep from OBT's.

-R.M. Harris - File # 91-8-1496 - 1991
FND. ½" Rod.
20" Maple N80°W 8.80'
10" Maple N53°E 19.60'
12" Maple S26°W 22.90'
6" Hemlock S60° 13.10'
-Rec. Survey L.2, P. 331 - R.M. Harris - 1992
FND. Iron Stake.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 - ¼ Corner common to Sec.'s 12&13, T26N,R15W. FND. ½" Rebar at soft spot in ground w/ some rotten wood at intersection of down fences N,S,E&W, this being apparent old anchor post position; fence intersection being the best available evidence of Haswell's perpetuation. Monument is in hardwood hills, 50± W. of top of hill. Iron accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 - Replace ½"x18" Rebar w/ 2" Alum. Cap on 5/8"x34" Rebar. Built ring of stone.
*N79°W 8.91' to set N&T in S. Side 23" S. Maple
*N46°E 19.38' to set N&T in SE. Side 11" S. Maple
*S71°E 13.08' to set N&T in SW. Side 6" Hemlock
*S21°W 22.88' to set N&T in E. Side 13" R. Maple
S26°E 41.42' to set N&T in W. Side 17" Beech - scribed 'XBT'
Set orange Carsonite post 1' S.

*New N&T's are in base of trees below nails by RMH.



Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 10/6/1998