

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 26N R 15W	M-5
	T 26N R 14W	A-5
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on April 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**


<u>M-5 &amp; A-5</u> -GLO - Set post Alvin Burt - 1839 Beech 13" N70°W 15L Do 5" S54°W 33L	-Co. Bk., P. 138-139 - F. Haswell - 1894 (Sec.13,T26N,R15W) Drove post 2' deep from OBT's
-GLO - Correct E. from post - Alvin & Austin Burt - 1839 T26N,R14W, Sugar 13" S65°E 8L Hemlock 11" N43°E 17L	-Co. Bk. II, P. 126 - F. Haswell (Sec. 7,T26N,R14W) Drove Iron Corner -R.M. Harris - File # 91-8-1496 - 1991 1" Pipe FND. 14" Maple N20°W 13.13', 9" Maple S70W 19.80' 14" Maple S25°W 11.10', 10" Maple S71°E 16.30'
	-Rec. Survey L. 2, P. 331 - R.M. Harris - 1992 FND. I. P.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-5 & A-5 -Standard Corner common to Sec.'s 12 & 13, T26N,R15W, & Sec.'s 7 & 8, T26N,R14W. FND 3/4" I.D. Iron Pipe apparently by Haswell and used by RMH. Fits distance N. well per Haswell. Distance E.&W. per Haswell is short; area very hilly. Find trace remains of fences N, W & E. CL. N-S 2 track is 8'± E. Accept Iron Pipe as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-5 & A-5 -3/4" I.D. Iron Pipe. Add ring of stone.  
 \* N26°W 13.74' to set N&T in E. Side 18" S. Maple.  
 \* S18°W 11.08' to set N&T in W. Side 16" S. Maple.  
 \* S75°E 16.33' to set N&T in S. Side 12" S. Maple.  
 N41°E 50.93' to set N&T in SE. Side 8" Beech - scribed 'XBT'  
 N71°W 22.67' to set N&T in S. Side 20" S. Maple - scribed 'XBT'  
 Reset found guard pipe SW. 0.45'  
 Set orange Carsonite post 1" N.  
 \*RMH nail & shiner along side.



Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 10/6/1998