

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 16 W.	K-12; L-12
2. PROPERTY CONTROLLING IN SECTION 36	T. 26 N. R. 16 W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 2, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-12 Fd. old 1 1/4" pipe at old fn. corner (fn. remains E-W-S). Fits survey of Sec. 36 by F. Haswell, 1910-1915±.
- L-12 Drove 1 1/2" pipe for center of Sec. 36 on straight line 1/4 line N & S & at double distance between N 1/4 cor. & 1/16 corner to N. Fits split-up of NE 1/4 of Sec. 36 & avg. line of occupancy of E-W 1/4 line to W and appears to fit F. Haswell split-up of Sec. 36. Center of sec. restored by this method is 8.4' S of straight line E-W 1/4 line.
- 8 Established 1/16 corner equidistant & on line between fd. W 1/4 corner Sec. 36 & reestablished center of Sec. 36, which fits F. Haswell split-up of Sec. 36.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12	L-12	8
Fd. 1 1/4" pipe & set cedar post w/loc. tag	Dr. 1 1/2"x60" pipe - cedar post w/loc. tag	Set 1"x36" pipe & cedar post w/loc. tag
12" Maple (clst. of 8)	5" Cedar S45°W 22.9	8" Cedar S38°W 14.9
7" Cedar S21°E 74.3	8" Cedar N28°W 23.9	6" Cedar N83°W 26.1
7" Cedar S21°W 53.6	7" Cedar N60°E 29.1	6" Cedar N40°E 18.2
	in W edge old N-S drn.ditch on true line W & N	5" Cedar S65°E 11.2
		in old fn. corn. fn. E-W-S on true line E-W


SIGNED BY Carl F. Roser DATE 4-18-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ BENZIE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET