

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	, T. <u>26</u> N. <u>●</u> , R. <u>16</u> W. <u>●</u>	<u>2; 5; 6; 7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 9, _____, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

7
Set 1"x36" pipe & cedar post w/loc. tag
24" Maple N35°W 33.5
18" Maple S27°W 54.8
9" Cedar S58°W 49.0
N-S fn. remains Due W 9'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Reestablished 1/16 corner midway & on line between ¼ corner W & sec. corner E; corner falls in old N-S fence & is in line w/row of large old maples to W & fits Haswell split-up of Sec. 36.
- 5 Estab. 1/16 corner on straight line N-S ¼ line in line w/old fence to W, which fits split-up of NE¼ Sec. 36 & appears to fit Haswell survey of Sec. 36.
- 6 Set 1" pipe at center of NE¼ of Sec. 36 per std. split-up of NE¼ Sec. 36. Corner falls in old fence corner, fence remains E-W-S.
- 7 Established 1/16 corner midway & on line between section corner N & ¼ corner S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2	5	6
Set 1"x28" pipe & cedar post w/loc. tag	Drove 1"x16" Rod, set cedar post w/loc. tag N89°54'E 33.0	Set 1"x30" pipe-cedar post w/loc. tag
14" Maple S04°E 105.0	4" Pincherry S51°W 51.80	6" Tamarack N31°W 19.8
24" Maple N88°W 76.43	7" Tamarack N11°W 105.05	6" Tamarack N56°E 11.2
in old N-S fence	Ctr. N-S b'top co. rd. Due E 8'±	6" Cedar S04°W 22.4
	Old cor.fn.post Due W 22'	

SIGNED BY Carl F. Roser 4-18-77 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ BENZIE COUNTY