

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 16 W.	J-12
2. PROPERTY CONTROLLING IN SECTION 35	T. 26 N. R. 16 W.	5; 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 11, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- J-12 Established center of Sec. 35 at intersection of ¼ lines. Possible corner fence post (fence remains N-W) is 16' ± E and 13' ± S.
- 5 Established 1/16 corner midway & on line between ¼ corner N and center of Sec. S.
- 9 Established 1/16 corner midway & on line between fd. ¼ corner to E & center of Sec. W. Corner fence post with fence remains N & E and wire W is 4.5' ± E & 22.3' ± S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12	5	Drove	9
Drove 1½"x54" pipe	Set 1½"x30" pipe & cedar	1"x36" pipe & ced. post w/loc. tag	
Dr. 6" Ced. post w/loc. tag	post w/loc. tag	12" Tamarack S48°W	21.9
Due N 1.0	6" Cedar N83°E 48.7	6" Cedar S87°E	35.6
Dr. 10" Ced. post	9" Cedar S40°E 42.5	6" Ash N56°E	17.0
Due E 1.5	5" Cedar S08°E 37.1		
Cor. in open tall grass marsh	Old N-S fn. Due E 5'±		
No other wits. available	Old fn. to E Due S 16'±		

SIGNED BY Carl F. Roser DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ BENZIE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET