

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 26 N. R. 16 W. ●	M-12
2. PROPERTY CONTROLLING IN SECTION.....	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 9, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-12 Reestablished position of E $\frac{1}{4}$ corner Sec. 36 (inaccessible, in Betsie River) equidistant and on line between section corners to N and S. U.S. notes call for corner being 40' N of S'ly edge of river; our corner position is 45'± N of S'ly edge of river.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WITNESS CORNERS TO INACCESSIBLE $\frac{1}{4}$ CORNER (M-12) IN BETSIE RIVER								
WITNESS CORNER #1			WITNESS CORNER #2			WITNESS CORNER #3		
Set 1 $\frac{1}{4}$ "x60" pipe & cedar post w/loc. tag N00°21'E 105.04' from M-12			Set 1 $\frac{1}{4}$ "x60" pipe & cedar post w/loc. tag S89°52'W 179.85 from M-12			Set 1 $\frac{1}{4}$ "x54" pipe & cedar post w/loc. tag S00°21'W 61.23' from M-12		
16" Ash	N76°W	21.8	10" Ash	N58°E	13.5	9" Maple	S17°W	32.7
14" Ash	N20°E	36.4	22" Maple	N30°W	5.7	24" Maple	S37°E	45.8
						Old N-S fence remains		
						Due W 6'±		


SIGNED BY Carl F. Roser DATE 4-18-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ BENZIE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET