

RECEIVED
 BENZIE COUNTY
 REGISTER OF DEEDS

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED
 10/16/2017 10:05:05AM
 REC FEE: \$30.00
 PAGE 1 OF 2
 64907

2017 OCT 16 AM 9 56

AMY J BISSELL
 REGISTER OF DEEDS

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson

Field Survey Date: August 25, 2016

For corner(s) in: Benzie County

Original Public Land Survey Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Property Controlling Corner			Corner Code
S <u>33</u>	T <u>27N</u>	R <u>13W</u>	<u>5</u>
S <u>33</u>	T <u>27N</u>	R <u>13W</u>	<u>12</u>
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Property Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Protracted Public Land Survey Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

5 – CN 1/16 corner section 33, T27N, R13W

12 – CS 1/16 corner common section 33, T27N, R13W

– None

– 2002 – unrecorded Survey – File No. 02-494 – R.
 Max Harris, PS #25845 – iron stake W/ cap set.

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

5 – CN 1/16 corner section 33, T27N, R13W

Set a stamped 2" aluminum cap on 5/8" X 34" rebar midway and online between F11 (a Benzie County Remon monument) and F12 (a found 1/2" rebar and cap #25845).

12 – CS 1/16 corner common section 33, T27N, R13W

Found a 1/2" rebar and cap # 25845 11'± West of gravel road centerline. N69°E 21.40' to a found a bent 1" square X 32" iron bar. Replaced with 1/2" rebar. Accepted the found 1/2" rebar and cap # 25845, and replaced it with a stamped 2" aluminum cap on 5/8" X 34" rebar.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

5 – CN 1/16 corner section 33, T27N, R13W


a stamped 2" aluminum cap on 5/8" x 34" rebar

N44°E 70.55' to set nail & tag in NW. side 16" R. Pine
S56°E 51.29' to set nail & tag in SW. side 23" W. Pine
S88°59'W 33.07' to a 2" aluminum cap on 5/8" x 34" rebar
N38°W 44.00' to set nail & tag in NE. side 7" S. Maple
N40°40'E 2.97' to found 1" iron bar

12 – CS 1/16 corner common section 33, T27N, R13W

a stamped 2" aluminum cap on 5/8" X 34" rebar

N39°E 45.43' to set nail & tag in SE. side 13" twin Maple
N69°15'E 21.40' to 1/2" rebar (replaced bent 1" sq. bar)
S26°E 54.16' to set nail & tag in N. side 4" Oak
West 32.97' to found 1/2" rebar & cap #25845
N79°W 26.75' to set nail & tag in S. side 14" R. Pine



Certifying Surveyor's Name

October 10, 2017

Date



Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601