

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED
 10/16/2017 10:05:07AM
 REC FEE: \$30.00
 PAGE 1 OF 2
 64907

RECEIVED
 BENZIE COUNTY
 REGISTER OF DEEDS

2017 OCT 16 AM 9 56

AMY J BISSELL
 REGISTER OF DEEDS

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson

Field Survey Date: October 10, 2016

For corner(s) in: Benzie County

Original Public Land Survey Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Property Controlling Corner				Corner Code
S _____	34	T 27N	R 13W	11
S _____	34	T 27N	R 13W	12
S _____		T _____	R _____	_____
S _____		T _____	R _____	_____

Property Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Protracted Public Land Survey Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13								●●						13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

11 – SW 1/16 corner section 34, T27N, R13W

12 – CS 1/16 corner common section 34, T27N, R13W

– 1966 – Survey of section 34 – prepared by Norton-Gourdie-Miller-Batzer, Inc. – Wm. B. Batzer, PS #13026. – iron corner.

– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

11 – SW 1/16 corner section 34, T27N, R13W

Searched for corner from Batzer survey. Found bed rail lying on ground in disturbed area. Set a stamped 2" aluminum cap on 5/8" X 34" rebar at a calculated position.

12 – CS 1/16 corner common section 34, T27N, R13W

Set a stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedures.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

11 – SW 1/16 corner section 34, T27N, R13W

a stamped 2" aluminum cap on 5/8" x 34" rebar

N33°E 65.02' to set nail & tag in NW. side 11" Sugar Maple
S76°E 10.34' to set nail & tag in S. side 14" Sugar Maple
S07°E 46.69' to set nail & tag in W. side 6" Ironwood
N55°W 25.28' to set nail & tag in SW. side 10" S. Maple


Set blue post with location tag 1' Southeast

12 – CS 1/16 corner common section 34, T27N, R13W

a stamped 2" aluminum cap on 5/8" X 34" rebar

N54°E 26.77' to found 1" pipe 2' above ground
S25°E 17.61' to set nail & tag in NE. side 15" Cherry
S67°W 102.95' to set nail & tag in SE. side 10" Sugar Maple
N40°W 72.82' to set nail & tag in NE. side 26" Sugar Maple

Set blue post with location tag 10' South



Certifying Surveyor's Name

October 10, 2017

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

