

Lansing - Forestry

Benzie County

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27 N. 13 E. W.	G-1; H-1; H-2
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4-11 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 _____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-1 Recovered corner - fits old line fence remains, N and Rd alignment for 3/4 MI to N.
- H-1 Restored corner on line and at prop. dist. to U.S., bet. the NE S-3 (1-1) and NW S-3(G-1)
- H-2 Recovered 1 1/2" pipe per Wolcott survey of Record (1938).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1		H-1		H-2	
Fd 1 1/2" well pt. Added DNR Mont. & Cedar Gd. Post		Set DNR Mon. & Cedar Gd. Post		Fd. 1 1/2" pipe. Added 1 1/2"x24" pipe & Cedar Guard Post	
12" Maple N88W 47.9'		7" Maple S61E 45.5'		8" R. Pine S88E 82.0'	
12" Maple N54E 34.5'		14" Maple N45W 7.4'		9" Tri-Maple N60E 14.7'	
14" Maple N40W 2.5'		24" Hemlock N 9E 37.7'		12" Maple S80W 69.0'	
14" Ironwood S12W 18.0'				1" pipe S89W 45.3'	
E-W B. wire Fn. Due N 2.5'					


SIGNED BY Carl F. Roser DATE 7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____