

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Benzie Located In _____ Corner Code # _____
 (County)

1. Public Land Survey
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section
 S 33 T 27N R 13W MC 33
 4
 S 33 T 27N R 13W 16

3. Miscellaneous Property in Section
 S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 27, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 6 | | 5 | | 4 | | 3 | | 2 | 1 |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

MC 33 | - GLO - Set Meander post - Alvin Burt - 1839
 4 | To West Side Lake - Set Meander Post
 Hem. 14° S40°W 16L
 Cedar 8° N45°W 21L
 - Norton, Gourdie, Miller, Batzer - Notes - 1966
 FND. Bed Rail Iron

16 - Plat of Colby's Burnt Mills Acres - W. Batzer - 1967
 L. 4 of Plats, P. 27 & 28 - Conc. Mon.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

MC 33 | - Meander Corner on W. side Bronson Lake on Twp.
 4 | line between Sec. 33, T27N,R13W & Sec. 4,
 T26N,R13W. - FND. 'L' Iron Bed Rail w/ 0.2' square
 top, 14' ± W of edge of Bronson Lake. Measure West
 196' ± 3' to bottom of bank, edge of lake bottom lands
 vs. 198' GLO to edge of swamp. Iron accepted as the
 best available evidence of the position of the original
 corner.

16 - Occupied E 1/16 Corner on S. line Sec. 33, T27N,R13W.
 FND. 1/2" Iron in Conc. Mon. per Plat. CL. Of NE-SW gravel
 Road is SE 30'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC 33 | - Iron Bed Rail
 4 | S5°W 14.09' to N&T in E. Side 9" Cedar
 S60°W 30.85' to N&T in NW. Side Tw. 19" R. Maple
 N53°W 12.98' to N&T in SW. Side 7" Hemlock
 N19°W 19.65' to N&T in W. Side 9" Cedar
 Set blue Carsonite post 1' S.

16 - Concrete Monument
 East 2.33' (2.35' - P) to 1/2" Iron in Conc. Mon.
 N50°W 16.33' to N&T in NE. Side 8" R. Oak
 S85°W 13.94' to N&T in S. Side 3" W. Pine
 S45°E 69.56' to N&T in NE. Side 6" W. Pine
 Set blue Carsonite post w/ Loc. tag 1' NW.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 10/6/1998