

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>13W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T _____ R _____	<u>2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S <u>19</u> T _____ R _____	<u>657' S. OF C-7</u>
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on OCTOBER 17, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 2 657' S. OF C-7



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 2 657' S. OF C-7
 FOUND IRON W/H. BRUNING PS CAP FOR THE NW COR OF NE1/4 OF NE1/4 OF S-19, FD. COR VERY CLOSE TO 1/2 MAY & ON LINE BETWEEN THE NE & NW COR'S OF S-19. FOUND 1/2" REROD W/J. GAVIN PS CAP FOR THE NE COR OF THE SE1/4 OF NE1/4 OF NE1/4 OF S-19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 2 657' S. OF C-7
 FD IRON W/PS CAP #10681. CTR. OF E-W WINDING SAND ROAD IS NORTH 15'. DROVE PK IN 4"x 4" TREATED POST BEHIND TEL. RISER N55°W 80.24'
 13° S. MAPLE S55°E 32.53'
 13° S. MAPLE S70°W 43.23'
 FOUND 1/2" REROD W/PS CAP #21568.
 6" S. MAPLE S30°E 50.80'
 8" R. PINE N75°E 50.80'
 DROVE ORANGE CARSONITE POST BY FD. 1/2" REROD W/PS CAP #21568 WEST 32.95'.
 CTR OF N-S 2-TRACK EAST 11'

Signed by Carl T. Kiiskila Date 4-9-97
 Surveyor's Michigan License No. 33981