

RECEIVED

JUN 23 1997

PARAS & NEUBAUER DIVISION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 13W

C-9

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, CARL KIISKILA, in a field survey on OCTOBER 2, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of row 9 and column C.

A. Description of original monument and accessories and/or subsequent restoration:

C-9

6.L.O. SET POST - 14" BEECH N36°E 23.1' AND 8" BEECH S36°W 23.1'. WM. BATZER, 1975 L.C.R.C. IN LIBER 1, PAGE 110 SET CONC. MONUMENT ON CTR. OF OLD N-S TRAIL AND ON EDGE OF WOODS TO EAST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9

FOUND CONC. MONUMENT FITTING WM. BATZER L.C.R.C. AND WITNESSES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9

FD 4" DIAMETER CONC MON WITH 1/2" REROD, ADDED BLUE CARSONITE POST W/LOC TAG. 10"R.MAPLE(CLP) N25°E 15.80'(DROVE SPIKE W/BCRP TAG W SIDE) 16" R.MAPLE N15°W 32.64'(DROVE SPIKE W/BCRP TAG W SIDE) 18" S.MAPLE S45°E 46.26'(DROVE SPIKE W/BCRP TAG NE SIDE) 16" S.MAPLE S05°E 42.39'(FD SPIKE E SIDE) 18" S.MAPLE S75°W 27.78'(REPLACED NAIL W/SPIKE-TAG NW SIDE) COR IS IN LINE W/NEWER STEEL POSTS & BARB/WIRE TO N & E. CTR OF TRAIL S'LY & NE'LY IS 10' EAST. † = PS, WM. BATZER 1975 WIT.



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-9-97