

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>13W</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 2, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19	●	20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 C-8
 6" L.O. SET POST - 6" SUGAR MAPLE S42°W 19.1' AND 6" BEECH N68°E 15.8'. WM. BATZER, 1975 L.C.R.C. IN LIBER 1, PAGE 11B FOUND 5" X 2" HIGH POST AND REPLACED IT WITH 1" X 30" PIPE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 C-8
 FOUND 3/4" GALV. PIPE FITTING WM. BATZER L.C.R.C. AND WITNESSES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-8
 SET 4"x 3/8" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP IN PLACE OF FD 3/4"x 30" IRON PIPE AND SET CARSONITE POST.
 #10" R. PINE N25°W 21.06' (DROVE SPIKE W/BCRP TAG NE SIDE)
 #10" S. MAPLE (CLP) N45°E 34.89' (DROVE SPIKE W/BCRP TAG SE SIDE)
 #13" R. PINE N60°E 64.55' (DROVE SPIKE W/BCRP TAG NW SIDE)
 #9" R. PINE S65°E 55.18' (DROVE SPIKE W/BCRP TAG NE SIDE)
 #19" B. CHERRY S05°E 2.38' (DROVE SPIKE W/BCRP TAG E SIDE)
 N-S WINDING TRAIL IS 150'+/- WEST. E-W WINDING TRAIL IS 65'+/- S.
 #= PS, WM. BATZER 1975 WIT.
 #= WIT BY OTHERS.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97