

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27NR 13W

A-6

T

T

T

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 17, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6

6.L.D. SET POST - 14" HEMLOCK N46°W 18.5' AND 14" BEECH S42°E
 46.2'. HAROLD R. BRUNING SET BENZIE CO. MARKER MIDWAY AND ON
 LINE BETWEEN NW CORNER AND SW CORNER OF SEC 18. DNR SURVEY
 CREW FOUND BENZIE CO. MARKER MAY 20, 1993 FITTING HAROLD R.
 BRUNING WITNESSES AND MAY 23, 1974 L.C.R.C. LIBER 1, PAGE 121.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6


FOUND BENZIE CO. MARKER PER HAROLD R. BRUNING L.C.R.C. LIBER 1,
 PAGE 121 AND WITNESSES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6

FD 1974 BENZIE CO MON, SET CARSONITE POST.
 19°BEECH N45°W 7.18' (DROVE NAIL W/TAG SW SIDE).
 15°BEECH N46°E 11.37' (FD NAIL W/TAG NW'LY SIDE)
 18°S.MAPLE N80°E 17.74' (FD NAIL W/TAG S. SIDE)
 17°S.MAPLE S05°E 15.30' (FD NAIL W/TAG E. SIDE)
 ATV TRAIL (NW - SE) IS 25' SOUTH.

* = PS H. BRUNING 1974 WIT.



Signed by Carl T Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97