

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27N R 13W A-10
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CARL KIISKILA, in a field survey on JUNE 27, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A-10

G.L.O. SET POST - 10° SUGAR MAPLE N63°E 19.1' AND 9° HEMLOCK 538°W 19.8'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-10

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN REESTABLISHED CORNERS TO THE NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-10

SET 4" x 36" CONC MON W/BENZIE CO RENON PROGRAM BRASS CAP AND SET CARSONITE POST.
 6" S. MAPLE N20°W 37.46'
 14" R. MAPLE N35°E 9.62'
 7" TRI. S. MAPLE S50°E 31.11'
 7" BEECH S87°W 43.13'



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97