

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>13W</u>	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on AUGUST 15, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	10			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11	●													
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

B-11

G.L.O. SET POST - 6" SUGAR MAPLE S22°E 12.5' AND 6" SUGAR MAPLE N18°W 13.2'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11

REESTABLISHED CORNER PRORATED TO U.S. RUN OUT BETWEEN FOUND SECTION CORNER TO THE EAST AND REESTABLISHED SECTION CORNER TO THE WEST AND IN CTR E-W SAND/GRAVEL ROAD. PS, N.HARRIS SET 1/2" REROD AT THIS POSITION BEFORE DNR SURVEY CREW REESTABLISHED THIS CORNER IN FIELD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11

SET 4"x 36" CONC MON W/BENZIE CO REMON PROGRAM CAP IN PLACE OF FOUND N.HARRIS 1/2"x 18" REROD. COR IS IN CTR OF E-W SAND/GRAVEL ROAD.  
 †15" B.CHERRY SOUTH 52.03'  
 †13" B.CHERRY (CLP 4) N50°W 68.82'  
 †7" MAPLE N05°W 31.50'  
 †19" TW.B.CHERRY S30°E 59.52'  
 SET CARSONITE POST W/LOC TAG BESIDE  
 FOUND 1/2" REROD SOUTH 33'  
 † = PS N.HARRIS WIT.



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-9-97