

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>13W</u>	<u>B-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property In Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 21, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-9

6.L.O. SET POST - 10" HEMLOCK S20°W 7.9' AND 16" HEMLOCK N74°E
 11.2'. NO EVIDENCE OF THIS 6.L.O. POST OR BEARING TREES WAS
 FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9

REESTABLISHED THE SOUTH 1/4 CORNER OF SECTION 19 ON LINE
 BETWEEN FOUND SE CORNER AND REESTABLISHED SW CORNER OF SECTION
 19 PRORATE TO 6.L.O. RUN OUT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9

SET 4" x 36" CONC MON W/BENZIE CO RENON PROGRAM BRASS CAP
 AND SET CARSONITE POST.
 5" TW. MAPLE N45°W 4.82' (DROVE SPIKE W/TAG NE SIDE)
 3" W. PINE N10°E 7.74' (DROVE SPIKE W/TAG E SIDE)
 3" W. PINE EAST 4.15' (DROVE SPIKE W/TAG S SIDE)
 16" MAPLE S30°W 28.53' (DROVE SPIKE W/TAG NW SIDE)
 N-S WINDING TRAIL IS 453' +/- WEST. FD OLD N-S BARB/WIRE IN TREES EAST 33' +/-.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97