

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 61

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE (County)	Located In:	Corner Code #
1. Public Land Survey	T 27N R 13W	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

15 Jan 1998 4:04:37 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey of OCTOBER 16, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-7

G.L.O. SET POST - 24" HEMLOCK N60 E 26.4', 15" BEECH N57 W 12.5', 24" HEMLOCK S50 E 42.9' AND 14" BEECH S17 W 36.96'. NO EVIDENCE OF G.L.O. POST OR BEARING TREES WAS FOUND. HAROLD R. BRUNING P.S. 1975 L.C.R.C. LIBER 1, PAGE 121 SET BENZIE CO. MARKER FROM G.L.O. CALLS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7

FOUND BENZIE CO. MONUMENT FITTING HAROLD R. BRUNING WITNESSES AND 1975 L.C.R.C.

Ratified by Peer Group
In accordance with P.A. 345
Chairman W.B. Smith
Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7

FD BENZIE CO MON, SET CARSONITE POST.
#10" TRI.R.MAPLE N30 E 65.74' (NAIL & TAG W. SIDE)
3"R.MAPLE S44 E 59.28' (NAIL & TAG NE SIDE)
#14"TW.R.MAPLE S02 W 57.57' (NAIL & TAG E. SIDE)
3" R.MAPLE S52 W 38.12' (NAIL & TAG NW SIDE)

= PS H.BRUNING 1974 WIT.



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-9-97