

APR 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 **LIBER 2 PAGE 65**

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>13W</u>	<u>B-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

15 Jan 1998 4:06:12 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES One

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7		●											
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-7

G.L.O. SET POST - 14" HEMLOCK S52°W 9.9' AND 14" BEECH N69°E 11.2'. HAROLD R. BRUNING 1974 - L.C.R.C. SET A BENZIE CO. MONUMENT ON LINE BETWEEN SE CORNER AND SW CORNER A DISTANCE OF 2640.00 FT. FROM THE SE CORNER. DNR SURVEY CREW MAY, 1993 FOUND BENZIE CO. MONUMENT FITTING HAROLD R. BRUNING WITNESSES AND 1974 L.C.R.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7

FOUND A BENZIE CO. MONUMENT FITTING HAROLD R. BRUNING WITNESSES AND 1974 L.C.R.C.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman [Signature]
 Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7

FD STD. BENZIE CO MON AND SET CARSONITE POST.
 #12" MAPLE (CLP 4) N70°W 15.13' (NAIL & TAG SLY SIDE)
 #9" TW. MAPLE N71°E 6.09' (NAIL & TAG SE SIDE)
 #9" MAPLE S10°W 10.03' (NAIL & TAG E SIDE)
 8" W.PINE S76°E 29.14' (NAIL & TAG N SIDE)
 9" W.PINE N07°W 57.67' (NAIL & TAG W SIDE)
 COR. FALLS AT N'LY EDGE OF WHAT LOOKS LIKE ABANDONED RD (NARROW 10' +/- WIDE TOTE RD) WITH SLIGHT CUT DOWN HILL TO WEST.
 † = PS, H. BRUNING 1974 WIT.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97