

SURVEY & REMONUMENTATION

APR 14 1998

LAND CORNER RECORDATION CERTIFICATE **2** PAGE **67**
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

BENZIE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|-------------|
| 1. Public Land Survey | T <u>27N</u> R <u>13W</u> | <u>B-11</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

15 Jan 1998 4:06:52 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES one

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on AUGUST 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11	●											
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-11

G.L.O. SET POST - 6" SUGAR MAPLE S22°E 12.5' AND 6" SUGAR MAPLE N18°W 13.2'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11

REESTABLISHED CORNER PRORATED TO U.S. RUN OUT BETWEEN FOUND SECTION CORNER TO THE EAST AND REESTABLISHED SECTION CORNER TO THE WEST AND IN CTR E-W SAND/GRAVEL ROAD. PS, M.HARRIS SET 1/2" REROD AT THIS POSITION BEFORE DNR SURVEY CREW REESTABLISHED THIS CORNER IN FIELD.

Ratified by Peer Group
 In accordance with P.A. 345

Chairman [Signature]

Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11

SET 4"x 36" CONC MON W/BENZIE CO REMON PROGRAM CAP IN PLACE OF FOUND M.HARRIS 1/2"x 18" REROD. COR IS IN CTR OF E-W SAND/GRAVEL ROAD.
 #15" B.CHERRY SOUTH 52.03'
 #13" B.CHERRY (CLP 4) N50°W 68.82'
 #7" MAPLE N05°W 31.50'
 #19" TW.B.CHERRY S30°E 59.52'
 SET CARSONITE POST W/LOC TAG BESIDE
 FOUND 1/2" REROD SOUTH 33'
 * = PS M.HARRIS WIT.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97