

**SURVEY & REMONUMENTATION**

APR 14 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE** LIBER 2 PAGE 68  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 13W B-13

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 BENZIE COUNTY  
 RECORDED

15 Jan 1998 4:07:05 PM  
 MICHELLE R. GRAY  
 REGISTER OF DEEDS  
 # PAGES One

Register of Deeds Stamp & File Number

I, CARL T. KIISKILA, in a field survey on OCTOBER 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-13

G.L.O. - SUGAR 10 IN. DIA. OR SECTION CORNER.  
 GEORGE STEEL, JULY 23/24, 1868 SURVEY OF S-6, T26N-R13W,  
 HENLOCK 14 S2W 46.2' AND BEECH 8 S39E 42.9'  
 HAROLD BRUNING, RLS #10681, 9-4-75 CERT. OF SURVEY - LI.1,  
 PG.393 "FOUND 1/2" I.P.; MAPLE 16" S81°W 30.21, NORWAY PINE 5"  
 S50°E 29.18', MAPLE 20" N23°E 42.00". H.BRUNING RECORDED COR  
 (SAME WIT) 12-30-1975 LI.1, PG.137.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13

FOUND 1/2" x 3/8" PIPE THAT FITS TWO OF H.BRUNING 1975 WIT.

Ratified by Peer Group  
 In accordance with P.A. 345

Chairman [Signature]

Date 7/24/1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13

SET 4" x 3/8" CONC. MON. W/BENZIE CO. REMON. PROGRAM BRASS CAP IN PLACE OF FD 1/2" PIPE. CTR. OF  
 E-W WINDING SAND RD. IS 14' NORTH.  
 8" S.MAPLE N25°W 67.14' (DROVE SPIKE W/BCRP TAG SW SIDE).  
 129" S.MAPLE N20°E 41.96' (DROVE SPIKE W/BCRP TAG OVER FD. OVERGROWN NAIL)  
 13" R.PINE S15°E 29.29' (DROVE SPIKE W/BCRP TAG NE'LY SIDE)  
 118" S.MAPLE S80°W 30.17' (DROVE SPIKE W/BCRP TAG OVER OVERGROWN NAIL N. SIDE)  
 DROVE BLUE CARSONITE POST W/LDC TAG NORTH 33'  
 FD 1/2" REROD W/CAP #25B45 SOUTH 32.98'



† = PS, H.BRUNING 1975 WIT.

Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-9-97