

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 70

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:07:29 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

For corners in

BENZIE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------|------------|
| 1. Public Land Survey | T <u>27N</u> R <u>13W</u> | <u>C-7</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7			●										
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
C-7

G.L.O. SET SUGAR MAPLE POST WITH NO BEARING TREES. WM. BATZER JR. 1971 L.C.R.C. IN LIBER 1, PAGE 109 FOUND A 1" IRON BAR. HAROLD R. BRUNING 1974 L.C.R.C. FOUND A 3/4" IRON INSIDE AN OLD 1 1/4" PIPE FITTING WM. BATZER L.C.R.C. & WITNESSES AND SET A BENZIE CO. MONUMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-7

FOUND BENZIE CO. MONUMENT FITTING HAROLD R. BRUNING L.C.R.C. AND WITNESSES.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 7/24/1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-7

FOUND BENZIE CO. MON.
#142" S. MAPLE N80°W 177.07' (DROVE NAIL W/BCRP TAG SSW SIDE)
FD 1/2" REROD N45°W 46.10' (PS CAP #25875 & 21568)
#127" S. MAPLE N24°W 75.76' (DROVE SPIKE W/BCRP TAG AT FD NAIL)#15" R. PINE N65 E
86.66' (DROVE NAIL W/BCRP TAG N'LY SIDE)
FD 1/2" REROD S45°W 47.32' (PS CAP #25875 & 21568)
CTR WINDING SAND/GRAVEL RD WEST IS 19' NORTH. CTR TRAIL SOUTH IS 24' EAST. COR IS IN LINE W/CTR
B. TOP RD LOOKING 300'+/- TO N & E.
= 1971 PS, WM. BATZER WIT
* = 1974 PS, H. BRUNING WIT.



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-9-97