

SURVEY & REMONUMENTATION

AUG 10 1994

COMMISSION

BENZIE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE LIBER **2** PAGE **013**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

26 JUL 94 3:40 P.M.

MICHELLE R. GRAY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Benzie

(County)

Located In:

Corner Code \neq

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>27N</u> R <u>13W</u> | <u>E-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, John B. Smendzulk, in a field survey on 12/21/93, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6: GLO set Ironwood Post - 30" Hemlock N61°E 19.80'. H.R. Bruning, 1973, set 5/8" x 24" rebar by single proportion between corners to north and south. He recorded this corner in 1973 and subsequent surveys through 1978. Bob Mitchell, 1985, in L.C.R.C. Liber 1, Page 217, found square stone with plow point 18" below road surface and raised to surface with rod and cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6: Reopened position found by Mitchell and found stone with plow point on west side below second gravel road bed. Also found remains of wood stake 28" below grade on west side of plow point. It appears that large stone was used to protect position of plow point and wood stake. H.R. Bruning corner is N45°E 6.09 feet. Bruning position was also recorded by Max Harris in 1992 in L.C.R.C., Liber 1, Page 286.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman John B. Smendzulk
 Date 12/21/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6: Pulled stone, plow point and stake remains and remonumented position of plow point and stake with 3" Ø concrete monument with Benzie County Remonumentation Program Brass Cap in monument box.

- Set Nail and tag in 10" Red Pine (with blaze) N43°W 45.82'
- Set Nail and Tag in 10" Red Pine West 44.38'
- Set Nail and Tag in Twin 6" White Pine S40°W 60.42'
- Found 1/2 x 18" rebar w/cap #10681 N83°E 37.53'
- Found 5/8 x 2" rebar w/cap #10681 N85°E 6.14'

CENTERLINE OF N-S ROAD IS 1' EAST

Signed by John B. Smendzulk Date 7/26/94
 Surveyor's Michigan License No. 30895

This corner was approved by the Benzie County Peer Review Group on 12/21/93.