

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 318

For corners in Almira Township

BENZIE Located in: Corner Code #
(County)

1. Public Land Survey T27N R13W E-8
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

4 FEB 2000 1:08:40 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

I, JOHN F. KORR JR., in a field survey on November 29, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1850 GLO - Survey - Set post for corner with two witnesses: Beech 8" - S82°W - 17.16'; Hemlock 6" - S85°E - 19.80'.
- Guy Langford, survey recorded in County Survey records Liber 2, Page 44 - Maple Post - No Wit.
- 1991 - G. Stowe, Certificate of Survey, Liber 2, Page 170, No Corner I.D. or witnesses.
- 1978 - Wm. Batzer, Certificate of Survey, Liber 1, Page 611. Set 1/2" X 24" iron rod at old fence intersection witnessed by: Maple 6" - S75°E - 18.07'; Maple 8" - N05°E - 28.65'; Maple 6" - N60°W - 33.97'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 - I found 1/2" X 24" iron rod, by Batzer and 4 witnesses called for in Section A above by Batzer in 1978. I accepted this corner as a locally accepted corner as no other evidence was found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- At the position of D-11, I set a Standard Benzie Co. Remonumentation Monument, witnessed by the following:
 - Ironwood 8" - S16°W - 34.83' - found spike
 - Basswood 14" - S50°E - 28.85' - found spike
 - Maple 14" - N10°E - 31.28' - set spike in East face, fence wire present.
 - Maple 20" - N42°W - 52.80' - found spike



Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/11/99

Signed by [Signature]
John F. Korr, Jr.

Date 12-23-99

Surveyor's Michigan License No. 24600