

**Remonumentation corner under P.A. 345, Michigan P.A. of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

ALMIRA TWP.

For corners in

BENZIE
(County)

Located in: Corner Code #

- | | | |
|------------------------------------|-----------------------------|-----------|
| 1. Public Land Survey | T <u>27</u> N R <u>13</u> W | <u>G4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LIBER **2** PAGE **166**

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

19 Jan 1998 2:49:32 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew T. Mokanyk, in a field survey on December 29 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

GC# 97480.01

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
August 1850 - GLO Surveyor - Set Hemlock post and two accessories:
N11°E - 11.2' - Beech 8"
S23°W - 22.4' - Hemlock 12"

July 1983 - Harold Bruning J#83-2635
Found 5/8" iron rod in c/A County Road and four accessories:
N57°W - 26.57' - H.Maple 10"
S70°W - 27.31' - H.Maple 18"
N83°E - 36.32' - S.Maple 10"
S75°E - 28.83' - H.Maple 16"

1994 - GTSC survey job #93-3146
Found 1/2" iron rod:
10" Maple N80E 36.30'
16" Maple S79E 28.80'
9" Ash S42E 44.55'
12" Maple N64W 25.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
December 1997 - Gosling Czubak
Remonumentation - Found 1/2" x 24" iron at fence line extension E-W. Benzie County Peer Group accepted position of 1/2" iron for corner G4. Removed 1/2" iron and set standard Benzie County Remonumentation Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G4 (East 1/4 corner Section 9, T27N-R13W)
Set standard Benzie County Remonumentation Monument and Monument box:
N57W 25.49' to nail/tag in N face 14" Maple
N80E 36.26' to nail/tag in N face 12" Maple
S75E 28.75' to nail/washer in N face 16" Maple
S42E 44.56' to nail/washer in SW face 12" Ash

Signed by Matthew T. Mokanyk Date 12-30-97
Surveyor's Michigan License No. 42063

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/18/97

