

**SURVEY & REMONUMENTATION**

APR 07 1998

**Remonumentation corner under P.A. 345, Michigan P.A. of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

ALMIRA TWP. SECTION  
For corners in

LIBER 2 PAGE 169

BENZIE (County)	Located In:	Corner Code #
1. Public Land Survey	T27NR 13W	G6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED  
19 Jan 1998 2:50:18 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES one  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Matthew T. Mokanyk, in a field survey on December 29, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

GC# 97480.01

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16	●	15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
August 1850 - GLO Surveyor - Set Beech Post and two accessories:  
N56°W - 18lk. - Sugar 10"  
S8°E - 29lk. - Beech 12"  
September, 1992 - Grand Traverse Surveying Company Job #92-746. Found iron. No accessories shown.

1978 H. Brunning - Set 1/2" x 24" iron/cap:  
P. Pole N65E 70.50'  
10" Maple N35W 71.60'  
12" Maple N23W 57.99'  
9" Maple N13W 90.15'

February, 1985 - Benzie Co. L.C.R.C. Liber 1, Page 216. Robert F. Mitchell found 2" strap iron 22" below road surface. Raised to road surface with a 1/2" rerod/cap #28417. "This position fits well with found corners 1/4 & 1/2 miles south."  
N65E Power Pole 64.17'  
N30W 12" Maple  
N47W 12" Maple  
S39W 1/2" rerod 6.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
December, 1997 - Gosling Czubak Remonumentation  
The Benzie County Peer Group accepted the position of the 2" strap iron for corner G6.  
Removed the 2" x 4" strap iron and set standard Benzie County Remonumentation monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
December 1997 - Gosling Czubak Remonumentation  
G6 (East 1/4 corner Section 16, T27N-R13W)  
Set standard Benzie County Remonumentation Monument and Monument box:  
S29E 97.80' to P.K. nail in P. Pole  
S39W 6.85' to 1/2" re-rod  
N30W 55.43' nail/washer 12" Maple  
N44E 127.84' to SW corner block bldg. foundation

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman [Signature]  
Date 12/29/97



Signed by Matthew T. Mokanyk Date 12-30-97  
Surveyor's Michigan License No. 42063