

MAR 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Almira Township

LIBER 2 PAGE 182

BENZIE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T27N R13W G-8
T____ R____
T____ R____

2. Property Controlling S____ T____ R____
in Section S____ T____ R____

3. Miscellaneous S____ T____ R____
Property in Sec. S____ T____ R____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

7 JAN 1999 4:05:32 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

I, JOHN F. KORR, JR., in a field survey on December 11, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

August 1850 GLO - Survey - Set post for corner with two Witnesses: Hemlock 14" - S35°E - 17.82'; Hemlock 12" - N20°W - 7.92'.

1969 - Peter G. Perla - Found 1" iron bar at centerline intersection of county roads, for work in Section 22.

1979 - Wm. B. Batzer - found iron bar, witnessed by: W. Pine 6" - S65°W - 51.31'; P.P. - N67°W - 28.72'; R. Pine 6" - N37°W - 56.95'; Maple 8" - S55°E - 48.50', for survey in Section 21.

1976 - Benzie Co. Road Commission. - Found 3/4" boat spike, @ intersection of centerlines, Witnessed: Jack Pine 6" - N29°W - 56.97'; W. Pine 4" - S65°W - 51.35'; Conc. Mon. - S45°E - 46.10'.

December 1979 - Corey Hughes, Survey in Section 22 J. # 79547 - found 3/4" Iron bar, witnessed by: P.P - N70°W - 28.42'; Jack Pine 8" - N39°W - 57.07'; Maple 20" - S55°E - 48.54'.

1988 - Benzie Co. Road Commission. - Found 3/4" iron rod, @ intersection of centerlines, Witnessed: Jack Pine 8" - N36° 30'W - 57.09'; W. Pine 6" - S66° 30'W - 51.44'; P.P - N68° 30'W - 28.41'; Conc. Mon. - S41°E - 46.04'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

December 1998 - I found a 3/4" iron rod at the intersection of county road centerlines, I also found 5 witnesses: W. Pine 6" - S66° 30'W - 51.44'; J. Pine 8" - N36° 30'W - 57.09'; P.Pole - N68° 30'W - 28.41'; Conc. Mon. - S41°E - 46.04'; Maple 24" - S50°E - 48.49'. I Accepted this corner with lack of any other evidence as a locally used and accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the position of G-8, I set a Standard Benzie Co. Remonumentation Monument, witnessed by the following:
W. Pine 6" - S66° 30'W - 51.44' W/Nail
J. Pine 8" - N36° 30'W - 57.09' W/Nail
P.Pole - N68° 30'W - 28.41' W/Nail
Conc. Mon. - S41°E - 46.04' W/Nail
Maple 24" - S50°E - 48.49' W/Nail
(as we dug, we removed a 2" x 1/4" flat steel bar 12" long)



Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/2/98

Signed by [Signature]
John F. Korrr, Jr.
Surveyor's Michigan License No. 24600

Date 12/29/98