

MAR 8 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 2 PAGE 183

For corners in Almira Township

BENZIE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T27N R13W G-9
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

7 JAN 1999 4:05:40 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

I, JOHN F. KORR, JR., in a field survey on December 14, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

August 1850 GLO - Survey - Set post for corner with two Witnesses: N80°E - 13.20' - Beech 10"; S67°W - 15.18' - Sugar 10".

1877 - D.F. Holden, L.1, P. 114, Reset from Org. B.T., No corner I.D.

March 1964 - Harold R. Bruning Benzie County Corner Registry No. 60, Benzie Co, Register of Deeds. Found a 1" x 22" iron pipe, John Eddleman, a long time resident in Section 22 stated that the pipe found occupied a position where a wood stake once existed as the corner. Set a 1" x 36" galvanized iron pipe with 4 Witnesses: W. Pine 3" - N56°17'W - 14.0'; W. Pine 22" - N24°21'E - 38.8'; H. Maple 20" - S85°34'E - 27.3'; H. Maple 7" - S 27°51'W - 22.8'; all with section scribes & NBT.

December 1979 - Corey Hughes, found Benzie Co. Mon. And 3 of Brunings witnesses as called for in the 1964 registry missing witness was the 3" W. Pine. Survey was for work in Section 22 J. # 79547.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

December 1998 - found Benzie Co. Mon. And 3 of Brunings witnesses as called for in the 1964 registry missing witness was the 3" W. Pine. I Accepted this corner with lack of any other evidence as a locally used and accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the position of G-9, I set a Standard Benzie Co. Remonumentation Monument, witnessed by the following:

- Maple 12" - S 30°W - 22.42' w/nail
- Twin Maple 10" & 6" - S75°W - 17.60' w/nail
- Twin maple 28" - S 80°E - 27.21 w/nail
- W. Pine 28" - N30°E - 38.02' w/nail

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | ● | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |



Ratified by Peer Group
In accordance with P.A. 346
Chairman [Signature]
Date 11/24/98

Signed by [Signature]
John F. Korr, Jr.
Surveyor's Michigan License No. 24600

Date 12/29/98