

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Benzie</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>E-11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Numb.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on July 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-11 - GLO - Set Post - J. Hunt - 1850  
 Beech 36" N66°E 40L.  
 Sugar 10" S50°W 35L.  
 - Old Co. Survey notes - G. Langford - No date  
 4" x 4" Ironwood Post set by original BT's  
 - DNR GLO BK. - Fence corner used as corner - 1960  
 - Gourdie- Frasier - Field notes - 1976  
 16" Basswood N70°W 15.09'  
 14" Basswood S20°E 9.07'  
 16" Maple N60°E 27.27'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 - Section corner common to sections 28,29,32. and 33. Found old 1 1/8" x 16 1/2" Solid Iron, 10" deep, in hardwood hills, per G.F. notes. Old fence remains to N and E. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-11 - Replaced FND. Iron with Benzie Co. Concrete Monument. Set Carsonite Post with location tag 1' S.  
 \* 16" Basswood N55°W 15.09'  
 \* 17" Sugar Maple Stp. N80°E 27.35'  
 \* 13" Basswood South 9.07'  
 9" Sugar Maple S20°W 6.73'  
 N88°E 16.93' to set N&T in N. Side 5" S. Maple  
 \* = Gourdie- Frasier & Assoc. witnesses.

Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 9/30/1998