

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|--|---------------------------|---------------|
| <u>Benzie</u> <small>(County)</small> | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>27N</u> R <u>14W</u> | <u>E -12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |



4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on July 13, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-12 - GLO - Set Qtr Post - J. Hunt - 1850
 - Beech 19" N88°W 15L.
 - Beech 18" N50°E 45L.
 - Old Survey notes - G. Langford - No date
 - 4" x 4" x 3' long Hemlock Post set by original BT's
 - Unrecorded Gourdie- Fraser Survey - File # 76891 - 1976 - DeLaMater Shows corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E - 12 - ¼ Corner common to Sec.'s 32&33, T27N,R14W. Found 3/4" x 28" Solid Iron for E 1/4 Corner S-32. Corner fits old Survey info on record at a SP position per Langford and GLO for S-33 and 1976 unrecorded Cert. of Survey by G. DeLaMater in S1/2 S-32. Found fence remains to E & W, scattered - 13'± N. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-12 - Replaced with Benzie Co. Concrete Monument - Set Carsonite Post with location tag 1.5' N.
 - * 18" Black Cherry N55°W 33.59'
 - * 8" Sugar Maple N15°W 24.15'
 - 4" Sugar Maple S40°E 13.42'
 - 6" Sugar Maple S50°W 5.08'
 - * = Witnesses by others



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 9/30/1998