

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____	_____
2. Property Controlling	S <u>33</u> T <u>27N</u> R <u>14W</u>	<u>12</u>
in Section	S <u>33</u> T <u>27N</u> R <u>14W</u>	<u>8</u>
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____



4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Craig W. McVean, in a field survey on JULY 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

12-CO. SUR. -G. LANGFORD-IRON BOLT 2"DIA. X 2.5' LONG-NO DATE 8- CO. SUR. -G. LANGFORD-MAPLE POST 4"X4"X3' LONG-BT-LYNN 6" S45°W 8L.-NO DATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

12- FOUND OLD 1 1/4" X2.5' LONG ROUND SOLID IRON FOR THE NE COR OF SE 1/4 OF THE SW 1/4 OF SEC 33. THE CORNER FITS OLD SURVEY NOTES FOR SUB'D OF SEC 33 PER LANGFORD FOR S1/4 AT SP POSITION. CENTER OF THE N-S GRAVEL ROAD IS 1' WEST. OLD FENCE REMAINS S & E IS 20' E, OLD FENCE REMAINS S & W IS 29' W +/-.

8 ESTABLISHED THE NE CORNER OF THE NW 1/4 OF THE SW 1/4 OF SEC. 33 AS PER STANDARD BLM PROCEDURE. THE CORNER FITS OLD CO.SURVEY IN SEC. 33. CORNER OF OLD B/WIRE FENCE REMAINS ON & IN GROUND IS 25' +/- N & 2' E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12 FOUND OLD 1 1/4" SOLID ROUND IRON 8 SET 5/8" X 34" REROD W/PS CAP & CARSONITE POST

44" SUGAR MAPLE N 25° W 65.30' WITH LOC. TAG.

FACE OF 6" SUGAR MAPLE N 20° E 53.3' 3" BEECH N 25° W 17.3'

13"SCOTCH PINE S 65° E 31.00' 5" BEECH N 05° E 13.9'

37" TRIPLE SUGAR MAPLE S 45 °W 34.37' 8" SUGAR MAPLE S 55° E 32.7'

SET CARSONITE POST W/ LOC. TAG W. 25' 6" SUGAR MAPLE S 55° W 14.2'

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 9/30/1998

