

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
JUN 23 1997

PAHAS & REGISTRATION DIVISION

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>6-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T _____ R _____	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on OCTOBER 21, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 6-13 15

U.S. G.L.O. - SET POST COR SEC'S 33 & 34; SUGAR 15 N58°W 8, BEECH 11 N37°E 33. FROM SOUTH INTER AT POST; BEECH B S49°E 48, BEECH 11 S58°W 55. OLD NOTES FOUND AT BENZIE CO. ROAD COMM FOR S-33 CALLS FOR - IRONWOOD 4"x 4"x 3' FOR SE S-33; ALSO OLD NOTES FD AT BENZIE CO. ROAD COMM FOR S-34 CALLS FOR BEECH POST FOR SW S-34.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 6-13 15

FOUND RR SPIKE FLUSH W/B.TOP RD, 5' SOUTH OF CTR E-W B.TOP & 4 WIT. TREES (W/MAIL & SHINER) ON B-3-93. ON 10-21-96 WE FD IRON W/PS CAP #30895 AT SAME LOCATION AS RR SPIKE & FITTING SAME 4 WITS. COR FITS 1992 CERT. OF SURVEY BY M.HARRIS, RECORDED IN L.2, P.250.

ESTABLISHED THE SE CORNER OF THE W1/2 OF SW1/4 OF S-34 PER STANDARD BLM PROCEDURE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 6-13 15

FD 1/2" REROD W/PS CAP #30895.
 #19" S. MAPLE N10°W 33.36'
 #16" S. MAPLE S55°E 61.30'
 #8" S. MAPLE S15°W 31.92'
 #7" S. MAPLE S45°W 52.86'
 SET BLUE CARSONITE POST W/LOC TAG BESIDE FD 1/2" REROD W/PS CAP SOUTH 33.0'
 #WIT BY OTHERS, FD MAIL & SHINER

SET 5/8"x 3/4" REROD W/PS CAP & BLUE CARSONITE POST W/LOC TAG.
 4" B.CHERRY (CLP 6) N45°W 4.72' (DROVE SPIKE NE SIDE)
 17" S.MAPLE N44°E 30.75' (DROVE SPIKE SE SIDE)
 10" W.S.MAPLE S40°E 58.17' (DROVE SPIKE NE SIDE)
 3" R.PINE S38°W 34.60' (DROVE SPIKE SE SIDE)
 CTR OF E-W WINDING B.TOP RD SOUTH 96'
 FN COR POST, W/B.WIRE ON GROUND, FN N & EAST IS 22' N & 10' E.

Signed by Carl T Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97