

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>J-13</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>34</u> T <u>    </u> R <u>    </u>	<u>14</u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-13

14

U.S. G.L.O. - SUGAR 16 IN IS QUARTER SECTION CORNER, SUGAR 30  
 N36°E 22. CAN FIND NO SIGN OF CORNER TREE OR WITNESS.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13

14

REESTABLISHED S1/4 CDR OF S-35 ON LINE BETWEEN FD FRANK HASWELL N1/4 CDR S-2, T26N-R14W & REESTABLISHED SE COR S-35, T27N-R14W (F.HASWELL, 1907, SAID "SET 1" GALV. IRON WELL POINT 27 1/2 LKS. E. OF 1/4 POST FOR T27N-R14W") AND AT HIS RECORD DISTANCE 27 1/2 LKS (18.5') WEST OF FD F.HASWELL PIPE. CENTER OF E-W WINDING SAND TRAIL IS 18' SOUTH.

ESTABLISHED THE NE CORNER OF SE1/4 OF SE1/4 OF SECTION 34 PER STANDARD BLM PROCEDURE. CTR OF UNUSED OLD LANE TO N IS 7' +/- WEST. OLD W/WIRE FM REMAINS N'LY IS 23' +/- EAST. B/WIRE FM TO EAST IS SOUTH 4' & B/WIRE FM WEST IS NORTH 4'. E-W FIELD DRIVE IS NORTH 18'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13

14

SET DNR MON & CARSONITE POST.  
 29" B. CHERRY N70°W 63.84'  
 11" R. PINE N22°W 39.37'  
 12" R. PINE N16°E 38.63'  
 N1/4 CDR S-2, T26N-R14W, FD F.HASWELL PIPE & REPLACED W/DNR MON IS S88°37'E, 18.15'

SET 5/8" x 3/4" RERDD W/PS CAP & SET CARSONITE POST W/LOC TAG.  
 36" S. MAPLE N65°W 36.80'  
 11" TW.S. MAPLE N60°E 6.88'  
 6" S. MAPLE S35°E 12.15'  
 21" S. MAPLE S45°W 33.06'

Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-9-97