

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W J-12, K-12

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-12

K-12

U.S. G.L.O. - SET IRONWOOD POST FOR 1/4 SEC. CORNER; BEECH B
S18°W 16, SUGAR 14 N19°E 26. NO SIGN OF POST OR WIT'S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-12

K-12

ESTABLISHED THE CTR OF S-35 AT INTER OF 1/4 LINES. EYEBALL
INTER OF OLD FM REMAINS TO S & E IS 3' +/- EAST AND 1' +/-
SOUTH.

REESTABLISHED E1/4 COR S-35 ON FENCE LINE TO WEST & ON LINE
BETWEEN FD SEC COR 1/2 MILE TO N & REESTABLISHED SEC COR 1/2
MILE SOUTH. CORNER FALLS IN APPROX. CTR OF WINDING N-S TRAIL
RD. OLD FM CORNER ON GROUND (FM REMAINS N & W) IS 31' +/- 3'
WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12

K-12

SET 5/8" x 3/4" REROD W/PS CAP & CARSONITE POST W/LOC TAG.

2" SCOTCH PINE N35°W 19.56'
22" S.MAPLE S60°E 11.39'
17" S.MAPLE S20°E 23.72'
8" R.PINE S60°W 45.81'

SET 1" x 48" GALV. PIPE W/PS CAP.

16" TW. W.ASH N40°W 49.76'
12" S.MAPLE N20°E 40.43'
10" S.MAPLE S85°E 22.63'
19" BEECH S70°W 17.92'
SET CARSONITE POST W/LOC TAG WEST 16 1/2'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-9-97