

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27NR 14W L-10

T R

T R

T R

2. Property Controlling
In Section

S 22 T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL T. KIISKILA, in a field survey of OCTOBER 10, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-10

1



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-10

1

ESTABLISHED THE CTR OF S-25 AT INTERSECTION OF 1/4 LINES.
CORNER FALLS NEAR E'LY EDGE OF OPEN FIELD.

ESTABLISHED NW COR OF NE1/4 OF NW1/4 S-22 PER STANDARD BLM
INSTRUCTIONS. CTR OF E-W ORCHARD LANE IS 28' NORTH, NORTH EDGE
OF SPRUCE PLANTATION IS 20'+/- NORTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-10

1

DROVE 5/8"x 3/4" REROD W/PS CAP AND CARSONITE POST W/LCD TAG AND
PALCED RING OF STONES.

SET 5/8"x 3/4" REROD W/PS CAP AND CARSONITE POST W/LOC TAG.

8" ELM N18°E 59.19' (DROVE NAIL & TAG W. SIDE)

8" SPRUCE N60°W 8.62'

12" S.MAPLE N45°E 35.34 (DROVE NAIL & TAG NW SIDE)

6" SPRUCE N30°E 5.56'

9" TW.S.MAPLE N85°E 24.75' (DROVE NAIL & TAG N SIDE)

16" BASSWOOD SOUTH 48.92'

16" S.MAPLE S55°E 27.88' (DROVE NAIL & TAG SOUTH SIDE)

4" SPRUCE S55°W 4.34'

Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-9-97