

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-----------------------------|----------|
| 1. Public Land Survey | T <u>27</u> N R <u>14</u> W | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
In Section | S <u>25</u> T _____ R _____ | <u>8</u> |
| | S <u>36</u> T _____ R _____ | <u>1</u> |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on OCTOBER 10, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 8 _____ 1 _____



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 8 _____ 1 _____

ESTABLISHED THE SE CORNER OF SW1/4 OF NW1/4 SEC. 25 PER STANDARD BLM INSTRUCTIONS.

ESTABLISHED THE NW COR OF NE1/4 OF NW1/4 SEC 36 PER STANDARD BLM PROCEDURE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 8 _____ 1 _____

SET 5/8" x 3/4" REROD W/PS CAP & BLUE CARSONITE POST W/LOC. TAG.
 15" MAPLE (CLP 4) N20°W 53.95' (DROVE NAIL & TAG E SIDE)
 12" S. MAPLE N65°E 46.63' (DROVE NAIL & TAG S'LY SIDE)
 19" TW. S. MAPLE S50°E 14.36' (DROVE NAIL & TAG NE SIDE)
 2" BEECH S40°W 12.68' (DROVE NAIL & TAG SE SIDE)

SET 5/8" x 3/4" REROD W/PS CAP & CARSONITE POST W/LOC. TAG.
 6" S. MAPLE N40°W 41.33'
 24" S. MAPLE N10°W 45.44'
 6" TW. MAPLE S10°E 32.44'
 19" S. MAPLE (CLP 6) S75°W 22.70'
 CTR E-W SAND TRAIL NORTH 11'
 OLD E-W FM REMAINS (ON GROUND) SOUTH 29' +/-

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97