

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27NR 14W K-10

T

T

T

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL KIISKILA, in a field survey on SEPTEMBER 9 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
K-10

G.L.O. SET POST - 12" BEECH N35°E 20.5' AND 14" SUGAR MAPLE S38°W 19.8'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10

REESTABLISHED THE CORNER BY SINGLE PROPORTIONATE MEASUREMENT, MIDWAY AND ON LINE BETWEEN FOUND CORNERS TO THE NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10

SET 4" x 36" CONC MON W/BENZIE CO RENOM PROGRAM BRASS CAP AND CARSONITE POST.

29" TN.S. MAPLE N85°W 79.64'

3" B. CHERRY (CLP) N10°E 15.64'

2" B. CHERRY EAST 15.32'

2" TN.B. CHERRY S45°E 14.48'

WINDING SAND TRAIL NE - SW IS N45°W 114' +/- 6'.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97