

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on SEPTEMBER 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11

G.L.D. SET POST - 18" SUGAR MAPLE S75°W 21.1' AND 12" SUGAR MAPLE N32°E 21.8'. R. MAX HARRIS, RLS #25845, 1991 L.C.R.C. LIBER 1, PAGE 271 FOUND AXE HEAD AND STONE, RAISED WITH 1/2" IRON ROD. MICH. DNR FEB. 1993 FOUND 1/2" IRON ROD FITTING R. MAX HARRIS WITNESS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11

FOUND 1/2" IRON ROD FITTING R. MAX HARRIS 1991 L.C.R.C. AND WITNESSES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11

REPLACED FD 1/2" x 24" REROD & OLD AXE HEAD W/4" x 36" CONC.

MON W/BENZIE CO REMON PROGRAM BRASS CAP.

#12"W.PINE N40°W 43.69'

#10"R.PINE S32°E 61.33'

#7" MAPLE (CLP 5) S12°W 49.32'

#13"W.PINE S62°W 86.26'

SET CARSONITE POST W/LOC TAG SOUTH 33'

COR IS IN APPROX CTR SAND RD LOOKING TO EAST AND SW, CTR TRAIL NORTH IS

10' +/- EAST, CROOKED TRAIL WEST IS 24' +/- SOUTH.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97