

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W      K-11  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
 in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on AUGUST 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11

G.L.O. SET HEMLOCK POST - 14" SUGAR MAPLE S29°W 25.1' AND 12" BEECH N13°E 13.2'. R.MAX HARRIS, RLS #25845, FOUND 2" IRON PIPE PER JUNE 1991 CERTIFICATE. MICH. DNR FEB. 1993 FOUND 2" PIPE FITTING R.MAX HARRIS DISTANCES TO WEST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11

FOUND 1 1/2" IRON PIPE (PREVIOUSLY CALLED A 2" PIPE) 5' NORTH OF E-W TRAIL ROAD AND ON CTR TRAIL ROAD TO SOUTH. THE 1 1/2"(2") PIPE FITS R. MAX HARRIS RECORDED DISTANCE WEST, TO THE SW CORNER OF SECTION 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11

FD OLD 1 1/2"x 30" PIPE (PREVIOUSLY CALLED A 2" PIPE), REPLACED W/4"x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP.

11" TW.S.MAPLE      N50°W      63.22'  
 7" R.PINE            N25°E      58.17'  
 24" BEECH            N70°E      68.08'  
 9" R.PINE            S50°E      52.67'  
 SET CARSONITE POST W/LOC. TAG NORTH 33'



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97