

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>H-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 H-13

6.L.O. SET POST - SUGAR 16, N17°E 19(12.5'); SUGAR 15 N40°W 40(26.4'). NO EVIDENCE OF 6.L.O. POST OR BEARING TREES WAS FOUND. LAND SURVEYOR R. MAX HARRIS, PS #25845, JUNE 12, 1992 CERTIFICATE STATES HE SET THE 1/4 COR OF SECTION 34. BENZIE COUNTY ROAD COMMISSION SHOWS SIMILAR DISTANCES 1/2 MILE TO THE EAST AND WEST AS RECORDED BY R. MAX HARRIS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13

FOUND AND ACCEPTED A RR SPIKE AS SET BY P.S. R. MAX HARRIS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 H-13

FD SMALL RR SPIKE, REPLACED W/4" x 3/8" CONC MON W/BENZIE CO REMON PROGRAM  
 BRASS CAP. CORNER IS IN LINE W/CTR B.TOP RD LOOKING NORTH, CTR GRAVEL RD TO  
 EAST IS 14' N & CTR B.TOP RD WSW IS 6' NORTH.  
 #TEL. BOX POLE S59°W 72.03'  
 #36" S.MAPLE N63°E 77.82'  
 #28" S.MAPLE S70°E 43.85'  
 #POWER POLE S35°E 17.83'  
 FD 1 1/8" x 10" IRON ROD FOR N1/4 COR S-3, T26N-R14W S89°20'E 10.20'  
 FD RR SPIKE (RD P1) N00°09'E 6.4'  
 # PS, R. HARRIS 1992 WIT



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97