

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27N R 14W

M-13

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
In Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, CARL T. KIISKILA, in a field survey on SEPT. 27, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-13

G.L.O. - BEECH 7' S22°W 8 LKS (5.3'), BEECH 6' N21°W 27 LKS (17.8').  
 GEO. STEEL, JULY 23/24 1868 - N.B.T. HEMLOCK 12 N86°E 33 (21.8'); SUGAR 24 N27°W 60 (39.6').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13

REESTABLISHED SE COR 5-36 (4-TWP COR.) ON AVERAGE CTR LINE OF IRREGULAR 2-TRACK TO EAST & AVG. LINE OF 30' TO 33' OLD R/W FENCE TO EAST, THAT IS ON S'LY SIDE OF 2-TRACK TO EAST; AND ON LINE OF CEDAR POSTS & FENCE REMAINS TO SOUTH. CTR. OF TRAIL ROAD (SM - ME) IS 3' NW'LY. REMAINS OF OLD CORNER FENCE POST HOLE IS 30' SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13

SET 4" x 36" CONC. MON ENCASED IN STEEL PIPE W/CONS. DEPT. BRASS CAP.  
 8" TRI. MAPLE N15°W 29.0'  
 11" MAPLE (CLP-7) N45°E 23.4'  
 7" MAPLE (CLP-4) S75°E 49.6'  
 10" MAPLE N80°W 27.7'



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97