

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27</u> R <u>14W</u>	<u>L-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on JULY 3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-7
 G.L.O. SET POST - BEECH 6 S60°E 12 (7.9'), BEECH 9 N69°W 42 (27.7'). NO EVIDENCE OF G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7
 REESTABLISHED CORNER EQUIDISTANCE AND ON LINE BETWEEN FOUND SEC CORNER 1/2 MILE TO EAST AND REESTABLISHED SEC CORNER 1/2 MILE TO WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7
 SET 4" x 3/8" CONC. BENZIE CO. REMON MON
 W/BRASS CAP AND CARSONITE POST.
 7" S.MAPLE N20°W 6.48'
 16" BEECH N55°E 30.54'
 14" S.MAPLE S65°E 5.75'
 4" S.MAPLE S12°W 15.73'



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97