

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W I-12

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-12

B.L.O. - SET SUGAR POST FOR OR. POST; BEECH 6 S71°W 18 (11.9'), SUGAR 12 S78°E 10 (6.6'). OLD SURVEY NOTES FD AT BENZIE CO. RD. COMM. FOR S-34 CALLS FOR 1" PIPE BETWEEN 2 OLD STAKES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12

MI DNR SURVEY CREW ON 7-1-93 FOUND OLD 1" PIPE BURIED 1/2', 3' WEST OF CTR. OLD N-S LANE; OLD N-S WOVEN WIRE FENCE IS 25'+/- EAST. PIPE FITS SURVEY DATA PER OLD NOTES FD. AT B.C.R.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12

FD OLD BATTERED 1"x 29" PIPE, REPLACED W/4"x 36" CONC. MON.

W/BCRP BRASS CAP AND SET CARSONITE POST.

22° S. MAPLE N30°W 14.98'

5° S. MAPLE N15°W 27.09'

33° S. MAPLE N15°E 55.78'

14° S. MAPLE N75°E 22.11'

OLD 3-STRAND CROOKED BARB/WIRE FENCE W'LY IS 50'+/- 12' NORTH.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97