

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>K-8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on JULY 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8

G.L.O. SET POST - 18" HEMLOCK 546°E 11.9' AND 8" SUGAR MAPLE N61°W 23.1'. G.L.O. RANDOM SOUTH BETW. SEC'S 23 & 24 CALLS WERE *23.00 SMALL POND SURROUNDED BY MARSH, 28.50 OVER SAME + ASCEND HILL, 31.00 SUMMIT OF HILL 35 FEET HIGH"; 1/4 COR POST WAS SET AT 39.80 CH'S; WHICH LEAVES FROM 1/4 COR B.B CH'S (580') TO SUMMIT OF HILL AND WE MEAS. 513' +/- 20', AND 11.3 CH'S (746') TO S'LY EDGE OF POND AND WE MEAS 792' +/- 8'. NO EVIDENCE OF THIS G.L.O. POST OF BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN REESTABLISHED CORNERS TO THE NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8

SET 4" x 3/8" CONC MON W/BENZIE CO REMON BRASS CAP. SET CARSONITE POST.

4" W.PINE	N20°W	18.96'
4" W.PINE	N60°E	12.18'
3" MAPLE	S60°E	34.92'
2" W.PINE	S30°W	19.28'



Signed by Carl T Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97