

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>6-10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on JULY 10, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28	●	27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

6-10

6.L.O. SET POST - 8" BEECH N17°E 9.9' AND 8" BEECH S52°W 27.1'. NO EVIDENCE OF THIS 6.L.O. POST OR WITNESS TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-10

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN FOUND CORNERS TO NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-10

SET 4" x 3/8" CONC MON W/BENZIE CO REMON PROGRAM  
 BRASS CAP AND SET CARSONITE POST.

4" S.MAPLE	N06°W	18.74'
8" BEECH	N75°E	12.24'
12" S.MAPLE	S36°E	27.26'
6" S.MAPLE	S15°W	16.62'



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97