

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on OCTOBER 7, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-11

G.L.D. SET POST - 18" BEECH NO DISTANCE GIVEN AND 18" BEECH NO DISTANCE GIVEN. OLD SURVEY NOTES FROM SURVEYORS REC. NO 11, PAGES 100-101 SAYS "CEDAR POST 4"X 3" BLACK DIRT & CHARCOLE", SURVEYOR AND DATE UNKNOWN (DIST. ON MAP SHOWS COR. AT S.P. POSITION).  
 R. MAX HARRIS, P.S. #25845, 1992 L.C.R.C. LIBER 1, PAGE 281 REESTABLISHED BY SINGLE PROPORTIONATE MEASUREMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11

FOUND 1/2" IRON WITH R. MAX HARRIS CAP AND FITTING HIS WITNESSES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11

FD 1/2" x 18" REROD W/PS CAP, REPLACED W/4" x 36" CONC. MON W/BENZIE CO REMON BRASS CAP. DROVE ORANGE CARSONITE POST 1' SOUTH.  
 #14" S. MAPLE N20°W 46.05' (FD NAIL & TAG NE SIDE)  
 7" BEECH N45°E 38.84' (DROVE NAIL & TAG SE SIDE)  
 8" S. MAPLE S40°E 26.13' (FD NAIL & TAG SW SIDE)  
 9" S. MAPLE (CLP 4) S40°W 18.50' (FD NAIL & TAG SE SIDE)  
 CTR OF E-W SAND TRAIL RD IS 6' NORTH.

# = PS, M. HARRIS 1992 WIT.



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97